



MANUFACTURING CAPABILITY

BUILT UNDER COVER, INSTALLED IN DAYS

For accommodation villages, tourism cabins, worker housing and multi-dwelling developments — where programme certainty matters more than anything.

WHY THIS SUITS A DEVELOPMENT PROGRAMME

On a multi-unit programme the risk is not the build, it is the schedule. Modular removes most of what makes a schedule slip.

-
- 01 Manufacture runs in parallel with site works, rather than after them — the two critical paths become one.
 - 02 Weather cannot stop the build. Nothing is exposed, and no trade is waiting on a dry week.
 - 03 Repeatable units mean repeatable cost. The tenth unit is built the same way, by the same team, to the same checks as the first.
 - 04 On-site installation is measured in days, which cuts disruption, traffic management and neighbour impact.
 - 05 One contracting party is answerable for design, manufacture, delivery and installation.
-



STRUCTURE

-
- | | |
|----|--|
| 01 | Purpose-built modular carcass with heavy-duty external steel framing, produced to a structural engineer's design |
|----|--|
-
- | | |
|----|---|
| 02 | Seam-welded corrugated high-strength steel external wall and roof panels, corrosion and weather resistant |
|----|---|
-
- | | |
|----|--|
| 03 | Galvanised steel framed internal walls |
|----|--|
-
- | | |
|----|--|
| 04 | Heavy-gauge steel floor joists, bearers and corner posts for bracing and load capacity |
|----|--|
-
- | | |
|----|--|
| 05 | Pressed steel seam-welded roofing panels |
|----|--|
-

These are not shipping containers. The load-bearing capacity of a shipping container falls well below the safety standard required of a housing structure; our carcasses comply with architectural design standards.

INSULATION

01	Closed-cell polyurethane (R1.5) sprayed to internal walls and ceilings
02	Sisalation between the spray-on polyurethane and the adjacent internal steel frame, and over the ceiling frame
03	50mm Rockwool or fibreglass batts (R1.5) through all outer shell cavities and internal walls
04	Fire-rated plasterboard
05	Long-life anti-corrosive coating to carcass walls, roof and floor joists

WINDOWS AND EXTERNAL DOORS

01 Double glazing to aluminium framed windows and glass sliding doors

02 Keyed locks to all external doors

INTERNAL FIT-OUT

-
- | | |
|----|---|
| 01 | Compressed fibre cement flooring, glued and screw-fixed to steel floor joists |
|----|---|
-
- | | |
|----|---|
| 02 | Floating vinyl timber flooring with foam underlay throughout, excluding wet areas |
|----|---|
-
- | | |
|----|---|
| 03 | Plaster-lined walls throughout; fibre cement sheet to bathrooms |
|----|---|
-
- | | |
|----|---|
| 04 | Plasterboard to ceiling battens with shadow line detail |
|----|---|
-
- | | |
|----|---|
| 05 | European Beech architraves and skirting throughout, excluding wet areas |
|----|---|
-



| ——— INSTALLATION · CRANED ONTO FOOTINGS ——— |

EVERY HOME IN THE RANGE

ONE BEDROOM

MODEL	Bed	Bath	Area
ELSEY	1	1	20.4 m ²
ALTON	1	1	20.4 m ²
AVON	1	1	28.8 m ²
BELFORD	1	1	40.8 m ²

TWO BEDROOMS

MODEL	Bed	Bath	Area
MURRAY	2	1	40.8 m ²
SELINA	2	2	57.6 m ²
NORFOLK	2	1	80 m ²

THREE BEDROOMS

MODEL	Bed	Bath	Area
DAWSON	3	2	81.6 m ²
MIRANDA	3	2	81.6 m ²

FOUR BEDROOMS

MODEL	Bed	Bath	Area
CLAREMONT	4	2	122.4 m ²

Prices shown are list prices and are subject to change without notice, including for cost increases in imported product, raw materials or currency movement. Installed price covers delivery and installation of the modules; it does not cover site works, which vary with access, slope, services and council requirements, nor third-party reports such as soil tests, bushfire management plans or land capability assessments — these are quoted after a site assessment and invoiced as incurred. Floorplans and specifications may be varied without notice; dimensions are approximate. Furniture, floor coverings, window furnishings, landscaping, fencing, driveways and decking are indicative only and not included unless separately listed.

STANDARD, ALWAYS

PREMIUM IS THE SPECIFICATION

There is no cheaper version of a 6Homes home with the budget tapware in it. This list is what arrives, every time, on every design.

-
- 01 Double-glazed windows and doors
 - 02 Designer kitchens and bathrooms
 - 03 Your choice of tapware finishes
 - 04 Energy-efficient insulation
 - 05 Turnkey service from permits to handover
-

| ——— NO UPGRADES REQUIRED ——— |

FIRST CALL TO KEYS

01 INITIAL CONSULTATION

A free conversation about your vision, your block and your budget, and honest advice on whether modular suits the site.

02 DESIGN SELECTION

Choose a design, then customise interior finishes, fixtures and fittings so the home matches how you actually live.

03 SITE ASSESSMENT

Soil conditions, access and local regulations assessed, confirming feasibility and telling us exactly what your site needs.

04 PERMITS AND APPROVALS

We obtain the planning and building permits and manage the regulatory process so approvals do not stall the build.

05 CONSTRUCTION

Your home is built in our controlled factory environment, with progress photos throughout.

06 SITE PREPARATION

Foundations and services go in while the modules are being built. Running the two in parallel is where the months come off.

07 DELIVERY AND INSTALLATION

Modules are transported to site and craned into place, ready for occupancy shortly after.

08 HANDOVER

After final inspections and approvals, we hand over the keys.



COME AND STAND INSIDE ONE

Photographs only go so far. Five minutes in a finished home tells you what a floorplan cannot — the ceiling height, the joinery, the way the light lands.

DISPLAY SHOWROOM	878 Whitehorse Road, Box Hill VIC 3128
------------------	--

HEAD OFFICE	4/830 Whitehorse Road, Box Hill VIC 3128
-------------	--

PHONE	1800 6HOMES (646 637)
-------	-----------------------

EMAIL	sales@6homes.com
-------	--

WEB	www.6homes.com
-----	--
